

CLAY MACHINE SPARES - ZEBRA BRICKS (PTY) LTD - ASSET LISTING - April 2021

Item No	Description
CLAY BRICK PLANT - COMPLETE & FULLY OPERATIONAL	
A	Clay Hopper (1m High by 1.4m Wide by 3m Long - 2.2kW 400V)
B	Conveyor Belt - Clay Hopper to Hammer Mill (4.8m Long by 0.5m Wide - 3.0kW 400V)
C	Hammer Mill - Modular Pilot BR0605 (Incl 30kW Motor & VSD)
D	Conveyor Belt - Hammer Mill to Rotary Sieve (7.5m Long by 0.5m Wide - 3.0kW 400V)
E	Rotary Sieve (1.2m by 1.2 by 3.8 by 5mm - CMC Helical Reduction Box - 5.5kW 400V)
F	Clay Box Feeder (3m Long by 0.8m Wide by 0.6m High - 3.0kW 400V - VSD)
G	Coal Box Feeder (2.5m Long by 1.58m Wide by 1.0m High - 1.1kW 400V Vibrator)
H	High Volume Chevron Conveyor Belt - Box Feeders to Double Shaft Mixer (2.6m Long by 0.5m Wide - 2.2kW 400V - Reduction Gearbox)
I	Double Shaft Mixer (2.6m Long by 0.8m High by 0.5m Wide - 22kW 400v - DBS Radicon Reduction Box) - Completely Refurbished +/- 150Hrs
J	Meranda 450 (Similar to JC Steele 25B Extruder) - Clay Brick Extruder (4m Long by 1.4m High by 0.8m Wide - 75kW 400v - VSD - NMC Radicon Reduction Box) - Completely Refurbished +/- 150Hrs
K	Clay Strip Cutter (2m Long by 1.25 High by 0.8m Wide)
L	Clay Brick Cutter - Semi Automatic (2.3m Long by 1.4m High by 2.3m Wide - 3kW 400v)
M	Roller Conveyor and Frame (13m Long by 0.45m Wide by 0.55m High)
N	Complete Electrical Layout (Master DB 25kVA 400Amp Master with various CB's & Wiring)
O	Spares & Equipment (55Kw & 5.5kW 400V Motors, Manifold)
P	Pallets - Brick Cutting & Packing (150 Units)
Q	Moisture Content Analiser
R	Penetrometer

R995 000.00 TOTAL - Excl. VAT Ex-Site